

165 Water Street, South Norwalk, Connecticut

AGGRESSIVE PRICE REDUCTION



COMMERCIAL PROPERTY FOR SALE

- 53,168 Square Feet, Two Story Structure
- Additional Floors can be Added
- 1.85 Acre Parcel
- Zone: Industrial #1
- Parking: On-site for 100 cars
- Fully Air Conditioned, Passenger & Freight Elevator, Conveyor Belt
- Attractive Brick Exterior
- **New Asking Price: \$6,650,000**

Contact:

Bruce Wettstein, SIOR

Office: 203.226.7101 ext. 2

Email: bruce@vidalwettenstein.com

or David Fugitt, SIOR

Office: 203.226.7101 ext. 5

Email: david@vidalwettenstein.com

All information from sources deemed reliable and is submitted subject to errors, omissions, change of price, rental, and property sale and withdrawal notice.



SIOR

Individual Members

Society of Industrial and Office Realtors

VIDAL/WETTENSTEIN, LLC

719 Post Road East, Westport, CT 06880

www.vidalwettenstein.com

165 Water Street, South Norwalk, Connecticut

Located on Water Street near SONO Redevelopment and Norwalk Harbor

| | |
|--------------------------|--|
| <u>Utilities:</u> | All Public, water, sewer & natural gas |
| <u>Electric:</u> | 800 Amps 120/208/480 Volts 3 Phase 4 Wire |
| <u>Column Spacing:</u> | 30' |
| <u>Clear Height:</u> | 1 st fl: 11' 5", 2 nd fl: 12' 4" |
| <u>Loading Docks:</u> | 3 10' x 8' with load levelers |
| <u>Freight Elevator:</u> | 2,000 Lbs. |
| <u>Zone:</u> | Industrial #1 |
| <u>Building Size:</u> | 53,168 S.F. |
| <u>Land Area:</u> | 1.85 Acres |
| <u>Age:</u> | 1980 |
| <u>Parking:</u> | 100 On-site with additional available |
| <u>Tax Assessment:</u> | \$3,405,560 |
| <u>Mill Rate:</u> | 25.682 |
| <u>Taxes:</u> | \$1.65 SF |
| <u>Frame:</u> | Steel frame, concrete floors |
| <u>Exterior Wall:</u> | Brick veneer |
| <u>Foundation:</u> | Slab- no basement |
| <u>Roof:</u> | Flat, tar & gravel |
| <u>Heating Type:</u> | Forced air natural gas |
| <u>Air Conditioning:</u> | Full HVAC |

All information from sources deemed reliable and is submitted subject to errors omissions, change of price, rental, and property sale and withdrawal notice.



Individual Members
Society of Industrial and Office Realtors

VIDAL/WETTENSTEIN, LLC

719 Post Road East, Westport, CT 06880
www.vidalwettenstein.com

165 Water Street, South Norwalk, Connecticut



All information from sources deemed reliable and is submitted subject to errors omissions, change of price, rental, and property sale and withdrawal notice.




Individual Members
Society of Industrial and Office Realtors

VIDAL/WETTENSTEIN, LLC

719 Post Road East, Westport, CT 06880
www.vidalwettenstein.com

165 Water Street, South Norwalk, Connecticut



All information from sources deemed reliable and is submitted subject to errors omissions, change of price, rental, and property sale and withdrawal notice.



Individual Members
Society of Industrial and Office Realtors

VIDAL/WETTENSTEIN, LLC

719 Post Road East, Westport, CT 06880
www.vidalwettenstein.com



NOTES:


- The writer has been prepared in accordance with Sections 20-10 through 20-15 of the Regulations of the State of Connecticut and the "Standards for Survey and Map in the State of Connecticut" as adopted by the Connecticut Association of Land Surveyors. The writer is not responsible for the accuracy of the information shown on this map which is the responsibility of the person or persons who furnished the same to the writer. It is intended to depict property boundaries and location of improvements.
- Reference is made to Map titled "A. Built Plot With Proposed Addition Prepared for Trade, The Company, Norwalk - Connecticut", dated 02/14/2013, prepared by Raymond L. Redness, Inc. It is intended to depict property boundaries and location of improvements.
- Reference is made to Deed of Record found in Bk. 4079, Pg. 31 N.L.R.
- Area of parcel compiled from record = 80,387 SF or 1.8454 Acre
- Reference is made to Map 2506, 371, 5996, 4203, 4207, 4887 & 950 & 959 N.L.R.
- Reference is made to instruments of record on labeled notes.
- Building coverage - Location of underground utilities are not depicted herein.
- Property lies in an Inhabited No. 1 Zone.
- Owner of record is ONE HUNDRED SIXTY FIVE WATER STREET ASSOCIATES LLC

COMPILATION MAP
 DEPICTING
#165 WATER STREET
 NORWALK, CT
 PREPARED FOR
KLAFF'S, INC.

JOB NO.: 7707-11 DATE: 02/14/2013
 DRAWN BY: CM CHECKED BY:
 SCALE: 1" = 20'
 7707 - CLAMP AWAY
 02/14/2013

Redness & Mead
 22 WEST STREET NORWALK, CONNECTICUT 06851-2032
 (404) 442-1111
 www.rednessandmead.com

This document and maps thereon are void unless countersigned and sealed by the professional engineer or registered architect. Unprofessional actions under any jurisdiction will be reported to the appropriate regulatory authority.



DWB HOLDINGS LLC
 165 WATER STREET
 NORWALK, CT 06851-2032
 PER MAP 9100 N.L.R.
 Area = 2,506.56 SQ. FT. @ 0.0577 Acre

#165 WATER STREET
 TWO STORY
 BRICK & STEEL
 BUILDING

WELLS & ASSOCIATES, P.C.
 GREGORY J. DAY, P.E.
 165 WATER STREET
 NORWALK, CT 06851-2032
 PER MAP 9100 N.L.R.
 Area = 2,506.56 SQ. FT. @ 0.0577 Acre

WATER STREET

DAY STREET

NORTH WATER STREET

CITY OF NORWALK

165 WATER STREET

APPROXIMATE

SCALE

DATE

DRAWN BY

CHECKED BY

SCALE

DATE

DRAWN BY

CHECKED BY

SCALE

DATE

DRAWN BY

CHECKED BY

SCALE

DATE

DRAWN BY

CHECKED BY

SCALE

DATE

DRAWN BY

CHECKED BY

SCALE

DATE

DRAWN BY

CHECKED BY

SCALE

DATE

DRAWN BY

CHECKED BY

SCALE

DATE

DRAWN BY

CHECKED BY

SCALE

DATE

DRAWN BY

CHECKED BY

SCALE

DATE

DRAWN BY

CHECKED BY

SCALE

DATE

DRAWN BY

CHECKED BY

SCALE

DATE

DRAWN BY

CHECKED BY

SCALE

DATE

DRAWN BY

CHECKED BY

SCALE

DATE

SCHEDULE LIMITING HEIGHT AND BULK OF BUILDINGS
COMMERCIAL AND INDUSTRIAL
CITY OF NORWALK
PART 1

| ZONES | HEIGHT | | MINIMUM AREA | SIZE OF PLOT | | FRONT | YARDS | AGG. SIDE | | MAXIMUM BLDG AREA | FLOOR AREA RATIO MAXIMUM | RECREATION AREA | RESIDENTIAL DENSITY |
|------------------------------------|---|--|--|---|--|---|---|--|--|--|---|--|---------------------|
| | MAXIMUM | MINIMUM | | WIDTH | DEPTH | | | FRONT | REAR | | | | |
| East Avenue Village District | 2 1/2 stories & 35 feet; 3 stories and 35 feet for hotels on a parcel of three (3) acres or more | | 10,000 sq ft | 60 feet | 40 feet Subject to Sect 118-1000B | 10 feet | 25% subject to 118-500(B)(4) | 20%, minimum 15 feet, need not exceed 20 feet | 20% for buildings | | | | |
| Golden Hill Village District | 2 1/2 stories & 35 feet | | 5,000 sq ft | 50 feet | 5 feet | None | None | 10 feet except where residence zone abuts, then 10 feet per story or 20 feet whichever is greater, subject to 118-1000F | 35% for buildings, 80% for buildings and parking, 20% open space | 0.7 | 200 sq ft per dwelling unit, except for elderly & congregate hsg, 125 | 1,650 sq ft of lot area per dwelling unit | |
| Neighborhood Business | 2 1/2 stories & 35 feet | 2 stories and 25 feet, subject to 118-510 C(4) | 5,000 sq ft | 50 feet | 35 feet from centerline Subject to Sect 118-1000B | None except where residence zone abuts 10 feet per story or 20 feet whichever is greater, subject to | None except where residence zone or coastal waters about 10 feet per story or 20 feet whichever is greater, subject to | 10 feet except where residence zone or coastal waters about 10 feet per story or 20 feet whichever is greater, subject to 118-1000F | 35% for buildings, 80% for buildings and parking, 20% open space | 0.7 | 200 sq ft per dwelling unit, except for elderly & congregate housing 125 sq ft per dwelling unit | 1,650 sq ft of lot area per dwelling unit | |
| South Norwalk Business District | 12 stories & 150 feet | 2 stories and 25 feet, subject to 118-520 C(4) | None | None | 35 feet from centerline, except where 25% of the length of the block front is occupied by buildings on the street line or within one foot of the streetline, then no setback will be required. Subject to Sect 118-1000B | None | None | On interior lots, 10% need not exceed 10 feet beginning at second story sill level or more than 20 feet above centerline elevation of the street. None required on corner lots. | On interior lots, 90% beginning on second story sill level or more than 20 feet above centerline elevation of the street. | | | 1,650 sq ft of lot area per dwelling unit; 785 sq ft of lot area per dwelling unit for developments of 19 units or less, as per Section 118-520 (C)(1) | |
| Central Business Design District | Subareas A & B: 6 stories & 72 feet; with bonus: 8 stories & 100 feet, except that, in a design district development park, hotels to a maximum height of 12 stories and 150 feet Subarea C: 4 stories & 48 feet; with bonus: 6 stories & 72 feet | 2 stories & 25 ft; bldgs located within interior courtyards may be one (1) story | None, except in Subarea B, where a minimum of 20,000 sq ft is required | None, except in Subarea B, where a minimum of 60 ft is required | None, except that a setback of 20 feet is required for structures with office use fronting on the first floor. Except for structures in a Design District Development Park, all structures must be setback 10 feet above the sixth floor, subject to Sect 118-504D(1)(b) | None, except as noted in Sect 118-504D(1)(b) | None, except in Subarea C, where a minimum of 20% is required; need not exceed 20 ft | None, except as noted in Sect 118-504D(1)(b) and in Subarea C, where an average setback of 25 feet is required, not less than 15 ft | Subareas A & B: none Subarea C: 40% buildings, 80% buildings & parking 20% open space | Subarea A: 2.25, with bonus: 3.0 & Subarea B: 2.0, with bonus: 3.0, subject to Section 118-504D(1)(g) Subarea C: 1.0; with bonus: 1.5 | 150 sq ft per dwelling unit, may include balconies, courtyards, indoor recreational facilities, landscaped roofs and outdoor recreational areas | Subarea A: 1 dwelling unit per 500 sq ft of lot area; Subarea B: 1 dwelling unit per 800 sq ft of lot area; Subarea C: 1 dwelling unit per 1,300 sq ft of lot area | |
| Rowayton Avenue Village District | 2 1/2 stories & 35 feet, subject to Section 118-530(C)(8) | | 5,000 sq ft | 50 ft | 35 feet from centerline Subject to Sect 118-1000B | None | 40% subject to 118-530(C)(2) and (7) | 10 feet for bldg & parking, except where coastal waters abut, 15 feet | 35% for building, 80% for building & parking | 0.7, subject to Section 118-530(C)(7) | | | |
| Research and Development | 2 stories & 35 feet | | 10 acres | Such that a circle with a 400 ft diameter will fit on the lot | 80 feet from centerline Subject to Sect 118-1000B | 25% need not exceed 80 feet | 50% need not exceed 160 feet | 25% need not exceed 80 feet | 10% for buildings, 25% for building & paved areas | | | | |
| Silvermine Tavern Village District | See underlying zone for single family uses; Village District uses: Existing nonconforming buildings none; additions and new structures see B(2)(e) for single family cluster housing, maximum of thirty-five 35 feet to peak for barn structures | | See underlying zone for single family uses; Village District uses: 3 acres | | See underlying zone for single family uses and accessory uses; Village District uses: Existing nonconforming buildings none; additions and new structures 15 - 25 feet, subject to Section 118-531(D)(2) | See underlying zone for single family uses and accessory uses; Village District uses: Existing nonconforming buildings none; additions and new structures 15 feet, subject to Section 118-531(D)(2) | See underlying zone for single family uses and accessory uses; Village District uses: Existing nonconforming buildings none; additions and new structures 40%, subject to Section 118-531(D)(2) | See underlying zone for single family uses and accessory uses; Village District uses: Existing nonconforming buildings none; additions & new structures none except that a 25 ft rear yard is required for the parcel containing the store, subject to 118-531(D)(2) | See underlying zone for single family uses; Village District uses: 60% buildings & parking | | | See underlying zone for single family uses | |
| Industrial #1 | 4 stories & 50 feet; 6 stories & 72 ft on lots 30 acres or larger; Multifamily and mixed use developments subject to Section 118-700 B.2.(l)(i-i) | | 5,000 sq ft | 50 ft | 35 feet from centerline subject to Sect 118-1000B; except for multifamily and mixed use developments which shall be located not more than ten (10) feet from property line, subject to 118-700 C.(6) | None except where residence zone abuts 10 feet per story or 20 feet whichever is greater, subject to 118-1000F; None for multifamily and mixed use developments | None except where residence zone or coastal waters about 10 feet per story or 20 feet whichever is greater, subject to 118-1000F; None for multifamily and mixed use developments | 10 feet except where residence zone or coastal waters about 10 feet per story or 20 feet whichever is greater, subject to 118-1000F; None for multifamily and mixed use developments | 50% for buildings, 90% for buildings and parking; None for multifamily and mixed use developments in transit oriented developments | 1.0; 2.0 for multifamily and mixed use developments in transit oriented developments | 150 sq ft per dwelling unit, may include balconies, courtyards, indoor recreational facilities, landscaped roofs and outdoor recreational areas | Multifamily and mixed use developments subject to Section 118-700 B.2.(l)(i-ii) | |
| Light Industrial #2 | 4 stories & 55 feet | | 3 acres | None | 30 feet Subject to Sect 118-1000B | 30 ft except when bounded by residential zone, then 50 feet | 60 ft except when bounded by residential zone, then 100 feet | 30 ft except when bounded by residential zone, then 50 feet | 40% | | | | |
| Restricted Industrial | 4 stories & 55 feet | | 43,560 sq ft | 100 ft | 30 feet Subject to Sect 118-711C | None except where provided shall be | 10 feet | 10 feet | 50% | | | | |

ARTICLE 70, Use Regulations Controlling Industrial Zones

§ 118-700. Industrial Zone No. 1. [Amended effective 12-20-1944; 11-1-1962; 9-25-1981; 12-10-1982; 9-13-1985; 6-29-1990; 11-27-1991; 6-28-2002; 9-27-2002; 7-27-2012; 3-29-2013; 2-28-2014; 2-27-2015; 6-30-2017]

- A. Purpose and intent. The primary purpose of this zone is to provide areas which permit manufacturing and related uses, including warehouse, office, retail and single- and two-family housing. Heavy industrial uses would be allowed by Special Permit. The district is intended to provide low-scale industrial facilities interspersed with other uses and with the utilities and infrastructure necessary to support such industrial operations. The provisions of this zone are designed to recognize the need for manufacturing space while ensuring that these areas are compatible with adjacent residential neighborhoods and with the capacity of available infrastructure.
- B. Uses and structures.
- (1) Principal uses and structures. In an Industrial No. 1 Zone, premises shall be used and buildings shall be erected which are used, designed or intended to be used for one (1) or more of the following uses and no other. Any use or structure having a gross floor area of twenty thousand (20,000) square feet or more or requiring fifty (50) parking spaces or more shall be permitted, subject to the provisions of § 118-1451, Site plan review. Properties located within the coastal zone boundary, shall be subject to coastal site plan review and all other requirements of § 118-1110 herein.
 - (a) Manufacture, processing or assembly of goods which are not noxious or offensive due to emission of noise, pollutants or waste.
 - (b) Warehouse, storage and wholesale distribution facilities, including package distribution facilities [Amended effective 4-29-2016]
 - (c) Transportation and bus storage terminals.
 - (d) Public utility supply and storage facilities.
 - (e) Building materials sale and storage yards, including contractor's storage yards. A contractor's storage yard located in the Industrial #1 zone may be used for the storage of empty containers and refuse collection receptacles that are exclusively used for the collection and disposal of construction debris in the construction trade, subject to the provisions of Section 118-1451 Site Plan Review where:
 - i. Said contractor's storage is located within one hundred (100) feet of an existing Solid Waste Transfer Station that has been approved by the Department of Energy and Environmental Protection (DEEP) or its predecessor the Department of Environmental Protection (DEP); and
 - ii. Neither the contractor's storage yard nor the Solid Waste Transfer Station are adjacent to residentially zoned property; and
 - iii. Neither the contractor's storage yard nor the Solid Waste Transfer Station are located within one thousand five hundred (1,500) feet of Interstate 95 (I-95). [Amended effective 6-30-2017]
 - (f) Offices, including medical offices, banks and financial institutions and contractor's offices. [Amended effective 1-26-2001; 5-29-2015]
 - (g) All principal uses permitted in the Marine Commercial Zone.

- (h) Retail stores, personal and business service establishments, including restaurants and taverns.
 - (i) Printing establishments.
 - (j) Municipal sewage treatment facilities.
 - (k) Research and development facilities.
 - (l) All uses, including special permit uses, permitted in the C Residence Zone. [Amended effective 1-26-2001; 7-24-2015]
 - (m) Off-street parking facilities.
 - (n) Oil or petroleum storage facilities of twenty thousand (20,000) gallons or less, propane gas storage of thirty thousand (30,000) gallons or less and natural gas storage of thirty thousand (30,000) cubic feet or less.
 - (o) Indoor contractor parking facility, subject to submittal of environmental impact statement certified by a licensed civil or environmental engineer. [Added effective 3-29-2013, amended effective 12-19-2014]
- (2) Special Permit uses and structures. The following uses shall be permitted by Special Permit in accordance with the provisions of § 118-1450, Special Permits, and shall comply with the Schedule Limiting Height and Bulk of Buildings, Commercial and Industrial, [EN53](#) and any additional standards set forth herein:
- (a) Municipal utility plant or storage yard, as defined herein, oil and petroleum storage facilities of more than twenty thousand (20,000) gallons. [Added effective 9-27-2002]
 - (b) Gasoline stations and the sale and service of motor vehicles, subject to § 118-1010.
 - (c) Propane gas storage of more than thirty thousand (30,000) gallons and natural gas storage of more than thirty thousand (30,000) cubic feet, other than public utilities.
 - (d) Asphalt and concrete plants and recycling operations and rock crushing/processing facilities.
 - (e) Motor vehicle storage and junkyards.
 - (f) Solid waste transfer stations, recycling and composting centers and related facilities.
 - (g) Commercial recreation establishments.
 - (h) Hotels.
 - (i) Adult day care centers. [Added effective 8-31-2001]
 - (j) Helicopter landing sites, as an accessory use to a principal permitted use, subject to special permit review and to the following restrictions: the landing site shall be a minimum of 300 feet from a residence zone and flight operations shall be restricted to the hours of 7:00 am to 7:00 pm only. [Added effective 9-28-2001]
 - (k) Animal care centers, provided that the use is fully enclosed within a structure located on a lot a minimum of two acres in size, that the location of the use is located a minimum of one hundred and eighty (180) feet from a residential use as

certified by a licensed surveyor and that adequate provisions are made to control noise and odors emanating from the facility, subject to approval by the Zoning Commission. [Added effective 6-28-2002, amended effective 10-26-2012]

- (1) Multifamily dwellings, including mixed use developments, where the subject property is located within a designated area as shown on a map entitled "Designated Properties for Transit Oriented Development at South Norwalk Railroad Station." A defined recreation area of not less than one hundred fifty (150) square feet per dwelling unit shall be provided and located with due concern for the safety and convenience of the residents for whose use it is intended. [Added eff. 7-27-2012; amended effective 10-24-2014; 2-27-2015]
 - (i) Maximum Height: 6 stories and 72 feet above base flood level for multifamily and mixed use developments, provided that a minimum of ten percent (10%) the total number of units shall comply with Section 118-1050 Workforce Housing Regulation.
 - (ii) Residential Density: 800 square feet of lot area per dwelling unit for multifamily developments, provided that a minimum of ten percent (10%) the total number of units shall comply with Section 118-1050 Workforce Housing Regulation.
- (3) Uses which are not otherwise permitted in Subsection B(1) or (2) above shall not be permitted by variance in an Industrial No. 1 Zone.
- (4) Accessory uses and structures. Accessory uses and structures which are incidental to and customarily associated with the principal use of the premises shall be permitted subject to the following conditions:
 - (a) Outside storage as an accessory use shall be limited to a maximum height of twenty (20) feet, shall be limited in area to not more than twenty percent (20%) of the gross floor area of the principal structure, shall be confined to side and rear yards only and shall be effectively screened from view from adjacent properties.
 - (b) Testing and communications towers for research and development purposes to a maximum height of one hundred (100) feet. Testing towers may be attached to a building with the same maximum height restriction, provided that, if built on top of a building, the height of that building shall count in the calculation of the height of the tower. Towers shall not exceed length and width dimensions of sixty by sixty (60 x 60) feet.
 - (c) Commercial communication antennas are permitted as an accessory use when located on existing building or structure, subject to the height limitation of that zone, except that antennas mounted on existing buildings which meet or exceed the height limitation of that zone, may extend above the existing building height by no more than fifteen (15) feet. In addition, the color of the building shall be incorporated into the design of the antenna. [Added effective 4-25-1997]
 - (d) Municipal kennels are permitted as an accessory use when located on the same parcel as a municipal wastewater treatment plant, provided that the use is fully enclosed within a structure and that adequate provisions are made to control noise and odors emanating from the facility, subject to approval by the Zoning Commission. [Added effective 12-18-1998]

- (5) Additional standards for the Industrial No. 1 Zone.
- (a) Environmental impact. No use shall be allowed that is noxious or offensive by reason of the emission of smoke, particulate matter, noise, dust, glare, fumes, odor, ionizing radiation, vibration, heat or any other pollutant or waste. All industrial uses which may potentially emit such pollutants shall submit a written assessment of the environmental impacts of the proposed uses and a plan which demonstrates how the project will comply with local, state and federal environmental regulations.
 - (b) Environmental impact statement for indoor contractor parking facilities. No use shall be allowed that is noxious or offensive by reason of the emission of smoke, particulate matter, noise, dust, glare, fumes, odor, ionizing radiation, vibration, heat or any other pollutant or waste. A written assessment of the environmental impacts of the proposed uses shall accompany all applications for indoor contractor parking facilities and such statement shall be certified by a licensed civil or environmental engineer. [Added effective 12-19-2014]
 - (c) Sanitary facilities. Public sewer facilities shall be utilized and adequate provision for storm drainage shall be made as determined by the Commission.
 - (d) Illumination and noise. Exterior illumination and noise shall be controlled by design or screening so as not to intrude upon adjacent streets and properties.
- (6) All premises used as a junkyard or for storage of motor vehicles shall be maintained in strict accordance with the Regulation Concerning the Licensing of and Operation of Motor Vehicle Junk Yards, issued by the Commissioner of Motor Vehicles, State of Connecticut, as now in effect or as hereafter revised.
- C. Lot and building requirements. See the Schedule Limiting Height and Bulk of Buildings, Commercial and Industrial, [EN54](#) and all other applicable sections of these regulations, and in addition:
- (1) The area within required yards, except for vehicle and pedestrian accessways, shall be landscaped with lawns, trees and shrubs.
 - (2) No side or rear yard shall be required where a lot abuts a railroad right-of-way.
 - (3) Public access.
 - (a) New developments on lots adjacent to the inner harbor [EN55](#) shall provide public access to the waterfront. Public accessways shall be an average of fifteen (15) feet in width and in the form of landscaped walks, boardwalks or piers designed to encourage active use by the public. Where access along the waterfront would, in the determination of the Commission, expose the public to hazardous conditions, the Commission may consider alternative forms of access to be provided. Reasonable time-of-day restrictions may be established regarding such public accessways where justified for reasons of security or public safety.
 - (b) Where the principal use of the property is a single- or two-family dwelling or a water-dependent use, the public access requirement shall not apply.
 - (4) The height, bulk, location and use of all buildings in existence at the time of adoption of this section are hereby declared to be in conformance with the requirements of this section, provided that, if such buildings are destroyed by fire, explosion, act of God or act of public enemy to an extent exceeding fifty percent (50%) of their assessed value, they

may be reconstructed only if the height, bulk, location and use of the building is substantially as it had previously existed, subject to approval by the Director of Planning and Zoning, except as modified where necessary to conform to the Flood Hazard Zone and coastal area management provisions of these regulations. The owners of such property shall document by A-2 Survey or other means the height, bulk, location and use of the building as it had previously existed.

- (5) Single- and two-family dwellings shall comply with the Schedule Limiting Height and Bulk of Buildings, Residential: C Residence. [EN56](#)
- (6) Existing structures that do not comply with the schedule of height and bulk requirements are hereby declared to be in conformance with these regulations provided that such structures are maintained, rehabilitated, and integrated into the proposed development. [Added effective 7-27-2012]

D. Off-street parking and loading requirements. See §§ 118-1200 through 118-1260, except that:

- (1) The principal use and structure shall be located between the street and all parking facilities. Underground parking facilities, the roofs of which are less than three (3) feet above the center-line elevation of the street, shall be exempt from this requirement. Above-ground parking facilities, proposed for properties located in the “Designated Properties for the Transit Oriented Development at South Norwalk Railroad Station” area, that are within the Industrial No. 1 Zone District and “Flood Zone AE,” where new construction for residential dwellings at street level would be at or below base flood level, may be exempt from this requirement subject to the Commission finding that suitable architectural enhancements are provided to mitigate the exemption. [Added effective 7-27-2012; amended effective 2- 28-2014]
- (2) Designated Properties for Transit-Oriented Development (TOD) at South Norwalk Railroad Station developed for residential use shall provide a minimum of one (1) parking space per studio dwelling unit, one (1) parking space per one (1) bedroom dwelling unit and two (2) parking spaces per two (2) bedroom or larger dwelling unit provided that the amount of parking spaces provided shall in no event be less than an average of 1.30 parking spaces per dwelling unit. [Added effective 10-24-2014]


E. Sign regulations. See §§ 118-1290 through 118-1295.

§ 118-710. Light Industrial Zone No. 2. [Added effective 7-24-1958; amended effective 11-9-1959; 9-15-1975; 2-28-2003, 5-2-2003, 12-23-2005, 2-26-2007]

A. [Amended effective 11-27-1991; 2-28-2003] All regulations applicable to Industrial Zone No. 1 shall be applicable to Light Industrial Zone No. 2 with the following exceptions or additions:

- (1) Principal uses and Structures. Except as hereinafter set forth, the only use permitted in Light Industrial Zone No. 2 is light industrial manufacturing. All other uses are prohibited, except as noted below
- (2) Special permit uses and structures. The following uses shall be permitted by special permit in accordance with the provisions of §118-1450, Special Permits, and shall comply with the designated Schedule Limiting Height and Bulk of Buildings, Commercial & Industrial Part 1, unless otherwise stated, and the additional standards set forth herein: [Amended effective 12-23-2005]


WAREHOUSE



1ST. FLOOR
PLAN

WAREHOUSE

WAREHOUSE



2ND FLOOR
PLAN

design collaborative
architects, p.c.

KASPER ASSOCIATES, Inc.
ENGINEERS & LANDSCAPE ARCHITECTS

765 Fairfield Avenue - Bridgeport, Ct. 06604

SECOND FLOOR PLAN


PROPOSED INDUSTRIAL FACILITY

WATER STREET & DAY STREET - NORWALK, CONN.

Prepared For
TRUDY TOY COMPANY

JOB NO. 4441

| | | |
|-------------|-----------------|-----------|
| SCALE | 1/8" = 1'-0" | |
| DWG. DATE | Dec 19, 1983 | |
| DESIGNED BY | R.E. M.M. | |
| DRAWN BY | R.E. M.M., J.L. | |
| CHECKED BY | R.E.S. | |
| BY | DATE | REVISIONS |
| 1 | 1/28/84 | 1.00 |
| 2 | 1/28/84 | 2.00 |
| 3 | 1/28/84 | 3.00 |
| 4 | 1/28/84 | 4.00 |
| 5 | 1/28/84 | 5.00 |
| 6 | 1/28/84 | 6.00 |
| 7 | 1/28/84 | 7.00 |
| 8 | 1/28/84 | 8.00 |
| 9 | 1/28/84 | 9.00 |
| 10 | 1/28/84 | 10.00 |



SECOND FLOOR PLAN
SCALE: 1/8" = 1'-0"